

## Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
79.90	<p>To point of beginning.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p> <p>Not cultivated.</p>
<hr/>	
East on random through center of Sec. 21	
Variation $20\frac{1}{2}^{\circ}$ East	
<p>Commencing at <math>\frac{1}{4}</math> sec. cor. between secs. 20 and 21, Set temporary corners at 20, 40 and 60 chains and at</p>	
79.80	<p>Intersect the E. bdy. 23 lks. N of <math>\frac{1}{4}</math> sec. cor.;</p> <p style="text-align: center;">Thence</p> <p>N. <math>89^{\circ} 50'</math> W. on true line.</p>
19.95	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{16}</math> sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake <math>5\frac{1}{2}</math> ft. distant; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked <math>\frac{1}{16}</math> S on N. face.</p>
39.90	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake <math>5\frac{1}{2}</math> ft. dist.; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked <math>\frac{1}{4}</math> S on N. face.</p>
59.85	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{16}</math> sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake <math>5\frac{1}{2}</math> ft. dist.; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked <math>\frac{1}{16}</math> S on N. face.</p>
79.80	<p><math>\frac{1}{16}</math> sec. cor. point of beginning.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p> <p>Good farming land. Not cultivated.</p>