

Chains	
39.90	Deposited charred stake 12 ins. in the ground for $\frac{3}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{3}{4}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $\frac{3}{4}$ S on N. face.
59.85	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{3}{4}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
79.80	To point of beginning. Land, level, mostly. Soil, 1st rate.
79.92	East on random through $N\frac{1}{2}$ of sec. 16. Variation 21° East. Commencing at 1/16 sec. corner 20 chains N of 1/4 sec. corner between secs. 16 and 17 Set temporary corners at 20, 40 and 60 chains and at Intersect E. bdy. 55 lks. N. of 1/16 sec. corner. Thence N. 89° 36' W. on true line.
19.98	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{3}{4}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
39.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{3}{4}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked