

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	1/16 S on N. face.
59.94	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
79.92	To point of beginning. Land, level. Soil, 1st rate. Not cultivated.
<hr/>	
	East on random through S½ of Sec. 9. Variation 21° East. Commencing at 1/16 sec. corner 20 chains N of S.W. cor. of sec. 9. Set temporary corners at 20, 40 and 60 chains and at
79.85	Intersect E. bdry. 70 lks. N of 1/16 sec. corner. Thence N. 89° 30' W. on true line.
16.20	Wagon road bears N.
19.96	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 sec. corner marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post 5½ ft. distant and raised mound of earth 1½ ft. high, 3½ ft. base around it.
21.70	Wagon road bears N.W.
39.92	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground marked 1/16 S on N. face for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base around it.
45.00	Wagon road bears N.W.
59.88	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 sec. corner marked 1/16 S on N face; dug pits