

Chains	
63.25	Wagon Road North. mound of earth 1 1/2 ft. high, 3 3/4 ft. base around it.
79.85	To point of beginning. Land, rolling. Soil, 1st rate. Not cultivated.
<hr/>	
East on random through center of sec. 9.	Variation 21° East.
Commencing at 1/2 sec. corner between secs. 8 and 9	Set temporary corners at 20, 40 and 60 chains, and at
79.92	Intersect E. bdy. 70 lks. N. of 1/16 sec. corner Thence N. 89° 30' W. on true line.
14.50	Spring branch 5 lks. runs N.E.
19.98	Set basalt stone 12 x 8 x 8 inches, 8 ins. in the ground for 1/16 sec. cor, marked 1/16 S on N. face and raised mound of earth and stone 1 1/2 ft. high, 3 3/4 ft. base over it.
36.70	Wagon road bears N.W.
39.96	Set post 3 ft. long 3 ins. square, 24 ins. in the ground for 1/2 sec. corner marked 1/2 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post, 5 3/4 ft. dist. and raised mound of earth 1 1/2 ft. high and 3 3/4 ft. base around it.
56.50	Cross roads courses N.E. and N.W.
59.94	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. corner, marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post, 5 3/4 ft. dist., and raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base around it.
62.50	Grave yard.
79.92	To point of beginning. Land, level. Soil, 1st rate. Grass fair.
The remainder of this section is not fit for cultivation. Oct. 20, 1887.	