

Chains	
59.92	2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
74.70	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. distant, raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins square 12 ins. in the ground marked 1/16 S on N. face. Wagon road bears N.
79.90	To point of beginning. Land, level. Soil, 1st rate. Not cultivated.
79.80	East on random through center of Sec. 32 Variation 20° East. Commencing at 3/4 sec. corner between secs. 31 and 32 Set temporary corners at 20, 40 and 60 chains and at Intersect E. boundary 12 lks. S. of 1/4 sec. corner Thence S. 89° 55' W. on true line.
5.50	Tudle Willows creek dry, course N.
19.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. distant; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins square 12 ins. in the ground marked 1/16 S on N. face. Wagon road bears N. and S.
25.00	Deposited charred stake 12 ins. in the ground for 1/4 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. distant and raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins square 12 ins. in the ground marked 1/4 S on N. face. Wagon road course N and S.
54.50	Face.