

Chains	
79.88	<p>sec. corner; dug pits 18 x 12 ins. E. and W. of stake 5$\frac{1}{2}$ ft. dist. and raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p> <p>To point of beginning.</p> <p>Land, mostly level.</p> <p>Soil, 1st rate.</p>
80.00	<p>East on random through S$\frac{1}{2}$ of sec. 29.</p> <p>Variation 20-3/4° E.</p> <p>Commencing at 1/16 sec. corner 20 chains N. of S.W. cor., 20 chains N. of S.W. corner of Sec. 29</p> <p>Set temporary corners at 20, 40 and 60 chains, and at intersect E. boundary 7 lks. S. of 1/16 sec. corner.</p> <p>Thence</p> <p>S. 89° 57' W. on true line</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 12 ins. E. and W. of stake 5$\frac{1}{2}$ ft. distant; raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
22.25	<p>Enter field.</p>
32.75	<p>Dry creek.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 12 ins. E. and W. of stake 5$\frac{1}{2}$ ft. dist.; raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
44.00	<p>Fence bears N. and S.</p>
59.00	<p>Wagon road bears N and S.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 12 ins. E. and W. of</p>