

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
80.00	<p>stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $1/16$ S on N. face.</p> <p>To point of beginning.</p> <p>Land, mostly level.</p> <p>Soil, 1st rate. Well adapted to agriculture.</p>
79.80	<hr/> <p>East on random through center of sec. 29.</p> <p style="text-align: right;">Variation $20\frac{1}{2}^{\circ}$ East.</p> <p>Beginning at $\frac{1}{4}$ sec. corner between secs. 29 and 30,</p> <p>Set temporary corners at 20, 40 and 60 chains, and at</p> <p>Intersect E. boundary 26 lks. N. of $1/16$ sec. corner,</p> <p style="text-align: center;">Thence</p> <p>N. $89^{\circ} 49'$ W. on true line.</p>
6.00	<p>Wagon road bears N and S.</p>
19.95	<p>Deposited charred stake 12 ins. in the ground for $1/16$ sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 12 ins. in the ground 2 ft. long and 2 ins. square, marked $1/16$ S on N. face.</p>
33.00	<p>Creek dry, course N.</p>
39.90	<p>Deposited charred stake 12 ins. in the ground for $1/4$ sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on N. face.</p>
48.60	<p>Wagon road, bears N.W.</p>
59.85	<p>Deposited charred stake 12 ins. in the ground for $1/16$ sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 feet. long, 2 ins. square 12 ins. in the ground marked $1/16$ S on N. face.</p>