

Chains	
79.80	To point of beginning. Land, mostly level. Soil, good. Some grass.
79.72	East on random through $\frac{1}{2}$ of sec. 29. Variation 20° East. Beginning at 1/16 sec. corner 20 chains N of $\frac{1}{2}$ sec. corner between secs. 29 and 30. Set temporary corners at 20, 40 and 60 chains and at Intersect E. boundary 10 lks. N. of 1/16 sec. corner Thence N. 39° 56' W. on true line.
14.00	Leave field.
19.93	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E and W. of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.
32.25	Creek 10 lks wide runs N.
36.00	Church House bears S. 2.00 chs.
39.86	Set post 3 ft. long 3 ins. square 24 ins. in the ground for 1/16 sec. corner, marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.
59.79	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
79.72	To point of beginning. Land, generally level. Soil, good. Not cultivated.
Oct. 21, 1887.	