

Chains	
79.72	Intersect E. boundary 45 lks. N. of $\frac{1}{4}$ sec. corner Thence N. 89° 41' West on true line.
40	Wagon road bears N.W.
17.50	Dry bed of creek, course N.
19.83	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
26.70	Enter field N. and S.
32.50	Leave field and dry branch bed.
37.50	Tudde Willows Creek, 4 lks. bears N.
39.86	Deposited charred stake 12 ins. in the ground for 1/4 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/4 S on N. face.
49.00	Fence bears N.E.
59.79	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.
67.75	Fence bears N.W.
79.72	To point of beginning.
	Land, level.
	Soil, good. Cultivated.
	East on random through N $\frac{1}{2}$ of sec. 20.
	Variation 20° East
	Commencing at 1/16 sec. cor., 20 chains N of $\frac{1}{4}$ sec. cor. between secs. 19 and 20
	Set temporary corners at 20, 40 and 60 chains, and at Intersect E. bdy. 42 lks. N. of 1/16 sec. corner.
79.80	