

Chains	
14.00	<p>S. 89° 55' W. on true line. Thence Wagon road bears N. and S.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/8 ft. distant and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face, and raised mound of earth 1 3/8 ft. high, 3 3/8 ft. base over it.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/8 ft. dist.; raised mound of earth 1 3/8 ft. high, 3 3/8 ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
42.00	<p>Gulch bears S. 70° W.</p>
47.00	<p>Spring 180 lks. S. of line.</p>
57.00	<p>Gulch bears S.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/8 ft. dist.; raised mound of earth 1 3/8 ft. high, 3 3/8 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
80.00	<p>To point of beginning. Land, rolling. Soil, generally good. Not cultivated.</p>
79.80	<p>East on random through center of sec. 17. Var. 21 3/4° East. Beginning at 3/4 sec. corner between sections 17 and 18 Set temporary corners at 20, 40 and 60 chains, and at Intersect E. boundary 16 lks. S. of 3/4 sec. corner Thence S. 89° 55' W. on true line.</p>