

Chains	
19.90	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
31.15	Wagon road bears N.W.
37.50	Wagon road bears N.
39.80	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
59.70	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. distant; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
79.60	To point of beginning. Land, level or mostly so. Soil, 1st rate. Not cultivated.
79.60	Set temporary corners at 20, 40 and 60 chains, and at Intersect E. boundary 23 lks. N of 1/16 sec. corner Thence
5.10	Wagon road bears N.E.
16.00	Wagon " " N.
	N. 89° 50' W. on true line.