

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains		
	sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5½ ft. distant; raised mound of earth 1½ ft. high 3½ ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.	
70.00	Top of ridge.	
80.12	To point of beginning. Land, rolling. Soil, 1st rate. Not cultivated.	-50
West on true line through S½ of sec. 31.		
Var. 20-3/4° E.		
20.00	Set charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.	
40.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.	
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.	
76.75	Intersect W. boundary of Township 20 chains North of Twp. corner, and Deposited charred stake 12 ins. in the ground for 1/16 sec. closing corner; dug pits 18 x 18 x 12 ins. N., E. & S. of stake 5½ ft. dist.; raised mound of earth 2 ft. high,	