

## Sub-Subdivisions, T. 2 N., R. 33 E.

| Chains |  |
|--------|--|
|        | <p>of stake <math>5\frac{1}{2}</math> ft. distant; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked <math>\frac{1}{16}</math> S. on E. face.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p> <p>Not cultivated.</p>   |
|        | <p>West on true line through center of sec. 19.</p> <p style="text-align: right;">Variation <math>20\frac{1}{4}^{\circ}</math> East.</p>   |
| 6.50   | Draw bears N.  |
| 16.10  | Wagon road N.  |
| 20.00  | <p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{16}</math> sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake <math>5\frac{1}{2}</math> ft. distant; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked <math>\frac{1}{16}</math> S on N. face.</p> |
| 40.00  | <p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake <math>5\frac{1}{2}</math> ft. distant; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked <math>\frac{1}{4}</math> S on N. face.</p>   |
| 60.00  | <p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{16}</math> sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake <math>5\frac{1}{2}</math> ft. distant; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked <math>\frac{1}{16}</math> S on N. face.</p> |
| 76.30  | <p>Intersect W. boundary of Township 202 lks. N. of <math>\frac{1}{4}</math> sec. corner on E. boundary of sec. 24, and</p> <p>Deposited a charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> sec. closing corner; dug pits 18 x 18 x 12 ins. E. and W. of stake <math>5\frac{1}{2}</math> ft. distant; raised mound of earth <math>1\frac{1}{2}</math> ft.</p>                                      |