

Sub-Subdivisions, T. 2 N., R. 33 E.

<p>base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>	<p>40.00</p>
<p>Deposited charred stake 12 ins. in the ground for 1/4 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. distant; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/4 S. on N. face.</p>	<p>53.30</p>
<p>Wagon road bears N.W.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. distant; raised mound of earth 1 3/4 ft. long, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>	<p>60.00</p>
<p>Wagon road bears N.W.</p> <p>Intersect W. boundary Township, 2.68 chains N. of 1/4 sec. corner on E. boundary sec. 12, T. 2 N. R. 32 E., and</p>	<p>69.50</p>
<p>Deposited charred stake 12 ins. in the ground for 1/4 sec. closing corner; dug pits 18 x 18 x 12 ins. N.E. and S. of stake 5 3/4 ft. distant; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/4 S.C.C. on E. face.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p> <p>Not cultivated.</p>	<p>76.50</p>
<p>West on true line through N 1/2 of sec. 18.</p> <p>Variation 20° East.</p> <p>Wagon road bears N.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. distant; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>	<p>6.20</p> <p>20.00</p>