

Sub-Subdivisions, T. 2 N. R., 33 E.

Chains		
27.50	Canon bears S.	-50
40.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.	
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.	
61.00	Gulch and Road S.	
76.50	Intersect E. boundary Township, 16.00 chains S. of corner to secs. 12 and 13 T. 2. N. R. 32 E. Deposited charred stake 12 ins. in the ground for 1/16 sec. closing cor.; dug pits 18x18x12 ins. N.E. and S. of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S.C.C. on E. face.	
	Land, rolling.	
	Soil, good.	
	West on true line through S½ of sec. 7. Variation 20° East.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.	