

Subdivisions, T. 2 N., R. 33 E.

(Examination of Corners.)

Chains

West between secs. 10 & 15, I pass 1/16 & 1/4 sec. cors.
Well preserved to cor. secs. 9-10-15 & 16. A post
26 x 4 x 4 ins. above ground marked S.10 T.2 N. on N.E.;
S.15.R.33 E. on S.E.; S.16 on S.W. & S.9 on N.W. faces.
No notches. I cut 3 on E. and 4 on S. edges. Pits
filled with sand and mound about gone.

West between secs. 9 & 16.
Passed 1/16 - 1/4 - & 1/16 corners; all right except pits
filled with sand at two of them. Found cor. secs. 8, 9,
16 & 17 post broken off and split fragment 24 x 4 x 4
ins. marked S.9, T.2 N. on N.E.; S.16.R.33 E. on S.E.;
S.17 on S.W. & S.8 on N.W. faces, with 4 notches on E.
& S. edges. Mound and pits partly destroyed, Reset post.

Found corner sections 20, 21, 28 & 29, a post 4 ft. long,
by 4 ins. square, marked S.21, R.33 E. on N.E.; S. 28
on S.E.; S.29 on S.W.; and S.20 T.2 on N.W. faces.
Cut 4 notches on E. & 2 on S. edges. Cut off the T & R
marks and put T. 2 N. on N. E. & R. 33 E. on S.E. faces.
Pits and mound very well preserved.

Going east bet. secs. 22 & 27, I passed 1/16, 1/4 & 1/16
corners; all well preserved and found cor. secs. 22, 23,
26 & 27 a post 48 x 4 x 4 ins., 24 ins. in ground, mark-
ed S.23, T. 2.N. on N.E.; S. 26 R.33.E. on S.E.; S27 on
S.W. and S.22 on N.W. faces. Cut 2 notches on S. and 2
on E. edges. Pits and earth mound partly destroyed.

For cor. 21-22-27 & 28, see page. 234.

April 30th, 1890.

Found cor. of 23-24-25 & 26 mound with pits 5½ ft. dist.
in each sec. Marked stake gone. Pits & mound in good
repair. Going North between secs. 23 & 24, found cor. to
secs. 13, 14, 23 & 24, a post 4 ft. long by 4 ins. square,
marked S.13 T.2 N. on N.E.; S.24 R.33E. on S.E.; S.23
on S.W.; S.14 on N.W. faces. Cut 1 notch on E. & 3 on