

Subdivisions, T.2 N.R. 33 E.

Examination of corners.

Chains

S. edges. Earth mound and pits partly destroyed.

Cor. 27, 28, 33 & 34. A post 4 ft. long by 4 ins. square, firmly set in ground marked S.27 T.2 N. on N.E.; S.34 R.33 E. on S.E.; S.33 on S.W.; S.28 on N.W. faces. No notches. I cut 3 on E. and one on S. edges. Pits and earth mound partially destroyed.

Cor. secs. 21-22-27 & 28. I found to be a post 4 ins. square by 2 ft. above ground, marked S.22 on N.E.; S.27, R.33 E. on S.E.; S.28 on S.W. and S.21 T.2 N. on N.W. faces. I cut off the T.2 N. and put it on the N.E. face; also the post had 3 notches on E. & 2 on S. edges. The pits are 5 1/2 ft. dist. in each sec. in good state of preservation; E. mound mostly gone.

May 1st, 1896.

TOPOGRAPHY

Through center of sec. 18. From closing corner 3/4 sec. cor. on W. boundary East.

Variation 20° East.

Tudle Willow Creek, course N. 20° W.

From cor. secs. 17, 18, 19 & 20. A charred stake, pits

5 1/2 ft. distant; stake gone.

North between secs. 17 and 18.

Variation 19° East.

A gulch (Tudle Willow) course N.W.

Line between 16 & 17.

From corner 16-17-20 and 21, which is a charred stake in earth mound with pit in each section 5 1/2 ft. distant; I run North between sections 16 and 17.