

Retracement-Resurvey of Subdivisions, T. 2, N., R. 33 E.

Chains

South, retracing line bet. secs. 14 and 15; at each 20.00 chs. make search for 1/16 sec. cors. and 1/4 sec. cor., but find no trace of same, and at 80.60 chs. fall 2 lks. W. of cor. of secs. 14, 15, 22 and 23, which is the butt of an old post, below the surface of the ground, agreeing very well with physical evidences of the cor. In place of the old post set a water worn basalt stone, 18x12x12 ins., 16 ins. in the ground, for cor. of secs. 14, 15, 22 and 23, marked with 3 notches on S. and 2 notches on E. edge.

From the temp. cor. of secs. 10, 11, 14 and 15, North retracing the line bet. secs. 10 and 11; at 20.00 chs. find no trace of the 1/16 sec. cor.; at 40.00 chs. find no trace of the 1/4 sec. cor.; at 50.69 chs. center of O.W.R.R. and N. Ry., bears N.85°16'W. and S.85°16'E.; at 60.00 chs. find no trace of the 1/16 sec. cor., and at 80.28 chs. fall 30 lks. W. of cor. of secs. 2, 3, 10 and 11, previously described.

From the cor. of secs. 2, 3, 10 and 11.

S.0°13'W., resurveying the line bet. secs. 10 and 11.

Over bottom land, through medium undergrowth.

- 10.00 Enter gravel bar, bears E. and W.
- 21.10 Umatilla River, 1.50 chs. wide, course NW.
- 22.60 Enter cultivated field, bears NW and SE.
- 29.61 Center of O.W.R.R. and N. Ry., bears N. 85°16'W. and S.85°16'E.
- 39.69 Fence, bears E. and W.; enter road.
- 40.22 Apportioned distance, point for 1/4 sec. cor. in road.  
Set a basalt stone, 18x15x12 ins., 16 ins. in the ground, for 1/4 sec. cor., marked 1/4 on W. face.
- 40.49 Fence, bears E. and W.; leave road; enter field.
- 40.53 As the point for 1/4 sec. cor. falls in road.  
Set an iron post, 3 ft. long, 1 in. diam., 28 ins. in the ground, for witness cor. to the 1/4 sec. cor., with brass cap marked

WC  
45  
1/4  
S10 | S11  
1917

- 65.15 Brook, 6 lks. wide, course N.60°W.
- 80.44 Apportioned distance.  
Set an iron post, 3 ft. long, 2 ins. diam., 30 ins. in the ground, for cor. of secs. 10, 11, 14 and 15, with brass