

Field Notes of the Survey of Tp. 2 N., R.
34 E., by Z. F. Moody, under his Contract
No. 145, dated April 23, 1871.

East Boundary.

Chains	From the South East corner to Township 2 North Ranges 34, East, I run North on East boundary of Sec. 36 Var. 20° 30' East	
35.75	Brook, 4 lks. wide, flows N. E.	-240
40.00	Set post for $\frac{1}{4}$ Section corner from which A fir 10 ins. in diam. bears E. 7 lks.	+75
80.00	Set stone 18 x 16 x 14 for corner to secs. 25, 36, 30 and 31. Land, hilly. Soil, 2d rate. Good grass.	-100
	North on East boundary of Sec. 25. Var. 19°30' East.	
40.00	Set stone 14 x 14 x 8 for $\frac{1}{4}$ Sec. corner	+150
80.00	Set stone 18 x 18 x 5 for corner to secs. 24, 25, 19 & 30. Land, hilly. Soil, 2d rate. Good grass.	-75
	North on East boundary of Sec. 24. Var. 18°30' East.	
40.00	Set stone 18 x 16 x 4 for $\frac{1}{4}$ Sec. corner	+140
80.00	Set stone 24 x 20 x 6 for corner to secs. 13, 24, 18 & 19. Land, hilly. Soil, 2nd rate. Good grass.	+100
	North on East boundary of Sec. 13. Var. 20° East.	
40.00	Set stone 18 x 14 x 9 for $\frac{1}{4}$ Sec. corner.	
80.00	Set stone 18 x 15 x 6 for corner to Secs. 12, 13, 7 & 18. Land, hilly. Soil, good 2d rate. First rate quality of grass.	
	North on East boundary of Sec. 12. Var. 20° East.	