

Subdivisions, T. 2 N., R. 34 E.

Chains	
79.97	To corner. Land, rolling. Soil, 1st rate. Good grass.
<hr/>	
	North between secs. 10 & 11.
40.00	Set post and made stone mound for $\frac{1}{4}$ sec. cor.
42.00	Brook, 8 lks. wide, flows N.W.
59.00	Wagon road, corner E & W.
65.00	Indian farm bears W. about 10 chs.
80.00	Set stone 18 x 12 x 5 for corner to secs. 10, 11, 2 & 3. Land, level. Soil, 1st rate. Good grass.
<hr/>	
	East on random between secs. 2 & 11. Var. 21°15' East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.00	Intersected N. & S. line 10 lks. S. of corner. S.89° 56' West on true line.
40.00	Set stone 14 x 12 x 7 for $\frac{1}{4}$ sec. corner.
80.00	To corner. Land, level. Soil, 1st rate. Good grass.
<hr/>	
	North on random between secs. 2 & 3.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.45	Intersected North boundary 16 lks. West of corner. S.0° 7' West on true line.
40.45	Set stone 17 x 15 x 10, for $\frac{1}{4}$ sec. corner.
60.00	Umatilla river, 250 lks., flows S. 70° W.
80.45	To corner. Land, rolling. Soil, 2nd rate.
June 3d, 1871.	
<hr/>	
	North between Secs. 33 & 34.
40.00	Set stone 18 x 17 x 9 for $\frac{1}{4}$ sec. corner.