

## Subdivisions, T. 2 N., R. 34 E.

Chains	
	North between Secs. 9 & 10.
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
80.00	Set stone 18 x 14 x 7 for cor. to secs. 3, 4, 9 & 10.
	Land, rolling.
	Soil, 1st rate.
<hr/>	
	East on random between secs. 3 & 10.
	Var. 21° 30' East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.84	Intersected N & S line 14 lks. N. of cor.
	N. 89° 54' W. on true line.
20.00	Dry bed of stream, N. 10° W.
39.92	Set stone 20 x 15 x 10 for $\frac{1}{4}$ S. cor.
79.84	To cor. in river bottom.
	Land, rolling.
	Soil, 1st rate.
<hr/>	
	North on random between Secs. 3 & 4.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.10	Intersected N. boundary at corner
	South on true line.
40.10	Set stone 14 x 14 x 8 for $\frac{1}{4}$ S. cor.
77.60	Umatilla river, 2 chs. wide, flows S.W.
80.10	To corner.
	Land, level. Soil, 2d rate.
	June 5, 1871.
<hr/>	
	North bet. secs. 32 & 33.
40.00	Set stone 16 x 16 x 12 for $\frac{1}{4}$ Sec. corner.
80.00	Set stone 18 x 18 x 10 for cor. to secs. 32, 33, 28 & 29.
	Land, some broken.
	Soil, 1st rate.
	Good grass.
<hr/>	