

Subdivisions, T. 2 N., R. 34 E.

Chains	The first half mile is on hill; 2d half on level land. Soil, 1st rate. Good grass.
	<hr/> East on random between Secs. 16 & 21. <div style="text-align: right;">Var. 20° East.</div>
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.10	Intersected N. & S. line 17 lks. N. of corner. N. 89° 53' West on true line.
40.05	Set stone 16 x 15 x 12 for $\frac{1}{4}$ Sec. corner.
80.10	To corner. Land, rolling. Soil, 1st rate. Good grass.
	<hr/> North between Secs. 16 & 17.
33.10	La Grand and Pendleton road, course E & W.
40.00	Set stone 17 x 13 x 10 for $\frac{1}{4}$ Sec. corner.
80.00	Set post and made earth mound for cor. to secs. 16, 17, 8 & 9. Land, level. Soil, 1st rate. Good grass.
	<hr/> East on random between secs. 9 & 16. <div style="text-align: right;">Var. 21° 30' East.</div>
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.00	Intersected N. & S. line 12 lks. N. of corner. N. 89° 55' West on true line.
4.50	Brook, 8 lks., flows N.W.
10.75	Wagon road, course N.E. & S.W.
40.00	Set stone 16 x 14 x 12 for $\frac{1}{4}$ Sec. corner.
80.00	To corner. Land, level. Soil, 1st rate. Good grass. There is a field to the north of this line.
	<hr/> North between secs. 8 & 9.
40.00	Set stone 16 x 14 x 8 for $\frac{1}{4}$ S. corner.
79.00	Enter river bottom.