

Subdivisions, T. 2 N., R. 34 E.

Chains	North between secs. 17 & 18.
34.00	La Grand and Pendleton road, course E & W.
40.00	Set post and made stone mound for $\frac{1}{4}$ Sec. corner.
80.00	Set post and made mound of earth for cor. to secs. 17, 18, 7 & 8.
	Land, rolling. Soil, 1st rate. Good grass.
	June 7, 1871.
	East on random between Secs. 8 & 17.
	Var. 21° East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.00	Intersected N. & S. line, 14 lks. S. of cor. S. 89° 54' West on true line.
23.00	Wagon road, course N.E. & S.W.
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
43.62	Brook, 8 lks. flows N.
80.00	To cor.
	Land, rolling. Soil, 1st rate. Good grass.
	West on random between Secs. 7 & 18.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.14	Intersected N & S line at corner. East on true line.
40.14	Set post and made earth mound for $\frac{1}{4}$ S. corner.
80.14	To corner.
	Land, level. Soil, 1st rate.
	North between Secs. 7 & 8.
40.00	Set stone 24 x 12 x 10 for $\frac{1}{4}$ Sec. cor.
80.00	Set post for cor. to secs. 7, 8, 5 & 6, from which A pine, 12 ins. in diam. bears N. 40° E., 37 lks. " balm, 20 " " " " S. 25° W., 95 lks.
	Land, level. Soil, 1st rate.
	East on random between secs. 5 & 8.
	Var. 21° 30' East.