

Exteriors T. 3 N., R. 34 East

Chains	
54.56	Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. & W. of cor. 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.
74.56	Set a post 48 x 4 x 4 ins., 12 ins. in the ground for cor. to secs. 31 & 32, T. 3 N. R. 34 E., marked T.3 N. S.31 on N.W.; R.34 E. S 32 on N. E.; T.2 N. on S. with 5 notches on E. and 1 notch on W. edges. Dug pits 18 x 18 x 12 ins. N.E. & W. of cor. 5½ ft. dist.; raised a mound of earth 2 ft. high, 4½ ft. base around post. Land, level. Soil, 1st rate. Some grass.
<hr/> South 89° 46' E. on S. bdy. Sec. 32. Variation 20° East.	
20.00	Deposited a charred stake 12 ins. in the ground for 1/16 sec. corner.; dug pits 18 x 18 x 12 ins. E. & W. of cor. 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
30.00	Canyon.
40.00	Set a basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for ¼ sec. cor. marked ¼ on N. face. Raised a mound of stone around it. Pits impracticable.
62.00	Set a post 36 x 3 x 3 ins., 12 ins. in the ground for 1/16 sec. cor., marked 1/16 S on N. face. Dug pits 18 x 18 x 12 ins. E. & W. of cor., 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base around it.
62.50	Ravine, course S.W.
80.00	Set a post 48 x 4 x 4 ins., 12 ins. in the ground for cor. to secs. 32 & 33, marked T.3 N.S32 on N.W.; R.34 E. S.33 on N.E.; T.2 N. on S. with 4 notches on E. & 2