

## Exteriors T. 3 N. R., 34 East.

Chains	
	<p>notches on W. edges, and dug pits 18 x 18 x 12 ins. N &amp; E &amp; W. of cor. 5½ ft. dist. and raised a mound of earth 2 ft. high, 4½ ft. base around post.</p> <p>Land, rolling.</p> <p>Soil, 1st rate. No timber. Poor grass.</p>
	<hr/> <p>South 89° 46' E. on S. bdy. Sec. 33.</p> <p style="text-align: right;">Variation 20° East.</p>
20.00	<p>Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E &amp; W of cor. 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
40.00	<p>Deposited a charred stake 12 ins. in the ground for ¼ Sec. Cor.; dug pits 18 x 18 x 12 ins. E &amp; W of cor. 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S on N. face.</p>
60.00	<p>Deposited a charred stake 12 ins. in the ground for 1/16 Sec. cor.; dug pits 18 x 18 x 12 ins. E &amp; W of cor. 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.</p>
80.00	<p>Set a post 48 x 4 x 4 ins., 12 ins. in the ground for cor. to secs. 33 &amp; 34, marked T.3 N.S. 33 on N.W.; R.34 E. S. 34 on N.E.; T.2 N. on S., 3 notches on E &amp; W edges. Dug pits 18 x 18 x 12 ins. N.E. &amp; W. of cor. 5½ ft. dist.; raised a mound of earth 2 ft. high, 4½ ft. base around post.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p> <p>Poor grass.</p>