

Exteriors T. 3 North, Range 34 East.

Chains	South 89° 46' E. on S. bdy. Sec. 34. Var. 21° East.
20.00	Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. & W. of cor. 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.
36.00	Wagon road.
40.00	Set a post 36 x 3 x 3 ins., 12 ins. in the ground for ¼ sec. cor., marked ¼ S. on N. face. Dug pits 18x18x12 ins. E & W of cor. 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base around post.
60.00	Deposited a charred stake 12 ins. in the ground for 1/16 Sec. cor.; dug pits 18 x 18 x 12 ins. E & W of cor., 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.
80.00	Set a basalt stone 10 x 8 x 8 ins., 6 ins. in the ground for cor. to secs. 34. & 35, marked 4 notches on W. and 2 notches on E. edges. Raised a mound of stone along-side. Pits impracticable. Land, rolling. Soil, 1st rate. Poor grass.
<hr/>	
	South 89° 46' East on S. bdy. of Sec. 35. Variation 21° East.
5.00	Gulch, course S. Ascend.
20.00	Top of ridge. Set a post 36 x 3 x 3 ins., 12 ins. in the ground for 1/16 sec. cor., marked 1/16 S. on N. face. Dug pits 18 x 18 x 12 ins. E & W of cor. 5½ ft. dist.; raised a mound of earth 1½ ft. high, 3½ ft. base around post.
40.00	Set a basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for ¼ Sec. corner, marked ¼ on N. face. Raised a mound