

Exteriors, T. 2 N., R. 34 East

Chains	North between Secs. 19 & 24.	
	Var. 20° East.	
17.50	Gulch, course E.	-100
25.15	" " "	-100
40.00	Set a basalt stone 12 x 10 x 10 ins., 8 ins. in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on W. face. Raised a mound of stone alongside; pits impracticable.	
43.90	Gulch, course E.	-100
80.00	Set a basalt stone 14 x 10 x 10 ins., 9 ins. in the ground for cor. to secs. 13, 18, 19 & 24. Marked 3 notches on N. & S. edges. Raised md. of stone alongside; pits impracticable.	
	Land, mountainous 80 chs.	
	Soil, rocky, 4th rate.	
	Scattering grass. No timber.	

	North bet. secs. 13 & 18.	
	Variation 20° East.	
32.40	Canyon, course E.	-400
40.00	Set a basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. corner, marked $\frac{1}{4}$ on W. face. Raised stone md. alongside; pits impracticable.	
47.50	Gulch, course E.	-200
60.00	Top of ridge. "	+400
71.60	Gulch, course "	-350
80.00	Set a basalt stone 16 x 14 x 12 ins., 11 ins. in the ground for cor. to secs. 7, 12, 13 & 18; marked 4 notches on S. and 2 on N. edges. Raised md. of stone alongside; pits impracticable.	
	Land, mountainous, 80 chs.	
	Soil, rocky, 4th rate.	
	No timber.	
	Good grass.	