

Exteriors, T. 2 N., R. 34 East.

Chains	GENERAL DESCRIPTION
	<p>This township is very rough in the S. Eastern part. The N. Western being gently rolling and well watered. There is very little timber excepting along the Umatilla River, which flows through the northern part. Good grass in every part.</p> <p style="text-align: right;">August 30th, 1887.</p>
	<p style="text-align: center;">Survey of Subdivisional Lines of Tp. 2, N., R. 34 East, by Currin & Noland, under their Contract, dated May 4, 1887.</p>
	<p>Beginning at cor. to secs. 35 & 36, T. 2, N., R. 34 E.,</p> <p style="padding-left: 40px;">I run</p> <p>North bet. secs. 35 & 36.</p> <p style="text-align: right;">Var. 21° East.</p>
40.00	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ S. corner, marked $\frac{1}{4}$ S. on W. face, from which</p> <p style="padding-left: 40px;">A pine, 16 ins. in diam. bears N. 80° E., 6 lks. dist., marked $\frac{1}{4}$ S.B.T.</p> <p style="padding-left: 40px;">A pine, 14 ins. in diam. bears N. 15° W. 36 lks. dist., marked $\frac{1}{4}$ S. B. T.</p>
80.00	<p>Set basalt stone 10 x 10 x 8 ins., 6 ins. in the ground for corner to secs. 25, 26, 35 & 36, marked with 1 notch on S and E edges; raised mound of stone over it.</p> <p>Pits impracticable.</p> <p>Land, level. Soil, 4th rate, rocky. Timber, scattering pine. Good bunch grass.</p>
	<p>East on random bet. secs. 25 & 36.</p> <p style="text-align: right;">Var. 18° East.</p>
40.00	<p>Set temporary $\frac{1}{4}$ Sec. cor., and at</p>
79.50	<p>Intersect Tp. line 50 lks S. of corner to secs. 25, 36, 30 and 31.</p> <p style="text-align: center;">Thence,</p> <p>S. 89° 39' West on true line</p> <p style="text-align: right;">Var. 22° East.</p>