

Subdivisions, T. 2 N., R. 34 E.

Chains		
	Ascend.	
28.00	Summit ridge N.W.	+300
39.00	Canyon, N.W.	-600
39.63	A large boulder 20 x 18 x 18 ins. above ground, which I mark $\frac{1}{4}$ on N. face with cross (X) on top and at exact cor. point for $\frac{1}{4}$ Sec. cor., and raised mound of stone over it. Pits impracticable.	
	Ascend.	
70.00	Summit of ridge N.	+800
79.25	Cor. to secs. 23, 24, 25 & 26. Land, rough & mountainous, 79.25 chs. Soil, 4th rate. Bunch grass. Timber, pine & fir in canyons.	
	North bet. secs. 23 & 24. Var. 19-3/4° East.	
7.50	Summit.	+600
40.00	Set basalt stone 10 x 9 x 8 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face and raised mound of stone over it. Pits impracticable.	
53.50	Gulch, N.W.	-200
70.00	Top of ridge N.W.	+450
80.00	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for cor. to secs. 13, 14, 23 & 24, marked with 3 notches on S. and 1 notch on E. edges; dug pits 18 x 18 x 12 ins., in each sec. 5 $\frac{1}{2}$ ft. dist. and raised mound of earth 2 ft. high, 4 $\frac{1}{2}$ ft. base over it. Land, rough and mountainous, 80 chs. Soil, varied, generally poor and gravelly. Bunch grass, good. No timber.	
	East on random bet. secs. 13 and 24. Var. 19°20' East.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner and at	
79.84	Intersect Tp. line at cor. to secs. 13, 24, 18 & 19. Thence, West on true line Var. 20° East.	