

Subdivisions, T. 2 N., R. 34 E.

Chains		
30.00	Summit ridge N.W. Descend.	+900
39.92	Set basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for $\frac{1}{4}$ S. cor., marked $\frac{1}{4}$ on N. face; dug pits 18 x 18 x 12 E. & W. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth over it.	
61.00	Bottom canyon N.W. Ascend.	-900
79.84	Cor. to secs. 13, 14, 23 and 24. Land, mountainous, 79.84 chs. Soil, 2nd rate, rocky. Good bunch grass.	
<hr/>		
	North bet. secs. 13 and 14. Variation 19°20' East. Descend.	
28.25	Canyon, N.W.	-600
32.50	Ledge of rock E & W 10 ft. high. Ascend.	
40.00	Set stone 16 x 14 x 4 ins., 10 ins. in the ground for $\frac{1}{4}$ S cor., marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 ins. N & S of stone $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
42.00	Gulch, N.W.	-50
54.50	Summit ridge N.W. Descend.	+250
80.00	Set basalt stone 18 x 12 x 6 ins., 12 ins. in the ground for cor. to secs. 11, 12, 13 and 14, marked with 4 notches on S and 1 notch on E. edges; dug pits 18 x 18 x 12 ins. in each sec. $5\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Land, mountainous, rough, 80 chs. Soil, good on N. side of hills. Grass, first rate. No timber.	
<hr/>		