

Subdivisions, T. 2 N., R. 34 E.

Chains		
60.00	Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of corner 5½ ft. dist.; raised a mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.	
63.00	Summit W.	†100
80.00	Set basalt stone 14 x 12 x 8 ins., 8 ins. in the ground for cor. to secs. 1, 2, 11 and 12, marked with 5 notches on S. and 1 notch on E. edges; dug pits 18x18x12 ins. in each sec. 5½ ft. dist., and raised mound of earth 2 ft. high, 4½ ft. base over it. Land, rolling hills. Soil, 1st rate on N.E. slopes; elsewhere, rocky. Grass, good.	
	East on random bet. secs. 1 and 12. Var. 19° East.	
40.00	Set temporary ¼ sec. cor. and at	
80.10	Intersect Tp. line 45 lks. N. of cor. to secs. 1, 12, 6 & 7. Thence N. 89° 41' W. on true line. Var. 20½° East.	
20.00	Summit ridge N.	†200
35.00	Gulch, N. Ascend.	-300
40.05	Set basalt stone 18 x 12 x 10 ins., 12 ins. in the ground for ¼ sec. cor., marked ¼ on N. face; dug pits 18 x 18 x 12 ins. E. and W. of stone 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it.	
55.00	Summit ridge, N.	†400
80.10	Cor. to secs. 1, 2, 11 and 12. Land, mountainous, rough, 80.70 chs. Soil, fair. Grass good.	