

Subdivisions, T. 2 N., R. 34 E.

Chains		
	North bet. secs. 1 & 2.	
	Ascend. Var. 19° East.	
12.00	Top of ridge N.W.	+250
	Descend.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. corner; dug pits 18 x 18 x 12 ins. N & S of cor., 5½ ft. distant and raised mound of stone covered with earth over it. In N. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.	
40.00	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for ¼ sec. cor., marked ¼ on W. face; dug pits 18x18x12 ins. N & S of stone 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.	
43.50	Umatilla River, 15 lks., runs West.	
56.65	Leave river bottom and ascend.	
57.70	O. R. & N. Co. R. R. West.	
64.50	Wagon road E & W.	
73.00	Intersect Tp. line, 6.70 chs. E. of cor. to secs. 35 & 36, T. 3 N. R. 34 E. and set post 4 ft. long, 4 ins. square, 24 ins. in the ground for closing cor. to secs. 1 & 2, marked C.C. T. 2 N.R. 34 E. on S.; S. 1 on E. and S.2 on W. faces, with 1 notch on E. and 5 notches on west faces; dug pits 18 x 18 x 12 ins. S.E. & W. of post 5½ ft. dist.; raised mound of earth 2 ft. high, 4½ ft. base around cor.	
	Land, rolling.	
	Soil, 1st rate. Timber, balm & cottonwood in bottom.	
	From the corner to Secs. 2, 3, 34 & 35 on the S. bdy. of the Township, I run	
	North bet. secs. 34 & 35.	
	Var. 20° East.	
5.00	Ravine and enter timber.	-50
22.00	Top hill and leave timber E & W.	+100
24.00	Enter timber and thick underbrush.	