

Subdivisions, T. 2 N., R. 34 E.

Chains		
38.00	Leave same.	
40.00	Set basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face; dug pits 18x18x12 ins. N & S. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
	Descend.	
47.50	Canyon, N.W.	-500
	Ascend.	
75.00	Top ridge N.W. and begin descent.	+400
80.00	Set basalt stone 12 x 8 x 6 ins., 8 ins. in the ground for cor. to secs. 26, 27, 34 & 35, marked with one notch on S and 2 notches on E. edges; raised mound of stone over it. Pits impracticable.	
	Land, rough and mountainous 80.00 chs.	
	Soil, 4th rate and rocky. Timber, pine and fir with heavy underbrush. No grass.	
	Sept. 1st, 1887.	
<hr/>		
	East on random bet. secs. 26 & 35.	
	Var. 21° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
80.30	Intersect N & S line 12 lks. N. of cor. to secs. 25, 26, 35 & 36,	
	Thence	
	N.89° 55' W. on true line.	
	Var. 18° East.	
14.00	Gulch, N.	-100
24.00	Wagon road, N & S.	
40.15	Set basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face and raised mound of stone over it. Pits impracticable.	
	Descend.	
74.50	Canyon N.W.	-600
80.30	Cor. to secs. 26, 27, 34 & 35.	
	Land, rough and mountainous, 80.30 chs.	