

Subdivisions, T. 2 N., R. 34 E.

Chains		
	<p>East on ran. bet. secs. 11 &amp; 14.</p> <p style="text-align: right;">Var. 20-3/4° East</p> <p>At 20 &amp; 40 &amp; 60 chs. set tem. 1/4 and 1/16 sec. cors. and at</p>	
79.50	<p>Intersect N &amp; S line 2 lks. S. of cors. to secs. 11, 12, 13 and 14,</p> <p style="text-align: center;">Thence</p> <p>S.89° 55' W. on true line.</p> <p style="text-align: right;">Var. 19 1/4° East.</p>	
2.50	Top ridge N.W.	+200
19.87	Set basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face; raised mound of stone over it. Pits impracticable.	
39.75	<p>Set basalt stone 12 x 9 x 6 ins., 8 ins. in the ground for 1/4 sec. cor., marked 1/4 on N. face; raised mound of stone over it. Pits impracticable, from which</p> <p style="text-align: center;">A cottonwood 10 ins. in diam. bears S.75° E., 10 lks. dist., marked 1/4 S. B. T.</p>	
40.00	Dry bed of creek N.	-100
59.62	Set basalt stone 14 x 12 x 6 ins., 8 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face and raised mound of stone over it. Pits impracticable.	
71.75	Ravine N.	-100
79.50	<p>Cor. to secs. 10, 11, 14 and 15.</p> <p>Land, rolling. Soil, 1st rate. Mostly tillable.</p>	
20.00	<p>North bet. secs. 10 and 11.</p> <p style="text-align: right;">Var. 20°45' East.</p> <p>Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on W. face; dug pits 18 x 18 x 12 ins. N &amp; S. of stone 5 1/2 ft. dist., and raised mound of stone and earth 1 1/2 ft. high, 3 1/2 ft. base over it.</p>	
23.00	Dry bed of creek N.W.	-100
40.00	Set basalt stone 16 x 10 x 8 ins., 10 ins. in the ground for 1/4 sec. cor., marked 1/4 on W. face; raised mound of	