

Subdivisions, T. 2 N., R. 34 East

Chains		
	stone over it. Pits impracticable.	
45.00	Top of hill W.	+150
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N and S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W. face.	
80.00	Set basalt stone 12 x 8 x 7 ins., 8 ins. in the ground for cor. to secs. 2, 3, 10 and 11, marked with 5 notches on S. and 2 notches on E. edges; dug pits 18 x 18 x 12 ins. in each sec., 5½ ft. dist., and raised mound of earth 2 ft. high, 4½ ft. base over it. Land, rolling. Soil, 1st rate. Good grass.	
	East on random bet. secs. 2 & 11. Var. 20° East.	
79.62	Set temporary cors. at 20, 40 and 60 chs. and at Intersect N & S line 30 lks. N. of cor. to secs. 1, 2, 11 & 12. Thence N. 89° 47' W. on true line. Var. 19° East.	
19.90	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. & W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.	
32.25	Gulch N.W.	-10
39.81	Set stone 16 x 10 x 8 ins., 10 ins. in the ground for ¼ sec. cor., marked ¼ on N. face; dug pits 18 x 18 x 12 ins. E. & W. of stone, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.	
41.35	Gulch N.W.	-10