

Subdivisions, T. 2 N., R. 34 E.

Chains	
50.00	Wagon road N.W.
59.71	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E & W of cor. 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
79.62	Cor. to secs. 2, 3, 10 and 11. Land, level. Soil, 1st rate. Good agricultural land.
	North bet. secs. 2 & 3. Var. 20° East.
12.20	Fence E & W. Enter field.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W face.
29.00	Leave field and enter river bottom and brush.
40.00	Enter Indian garden and set post 3 ft. long, 3 ins. square, 24 ins. in the ground for ¼ sec. cor., marked ¼ S on W. face; dug pits 18 x 18 x 12 ins. N & S of post, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.
49.00	Umatilla River, 125 lks. runs W.
51.70	O. R. & N. Co. R. R. W.
60.00	Set a basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on W. face and raised mound of earth and stone 2 ft. high, 4½ ft. base over it.
73.50	Intersect Tp. line 700 lks. E. of cor. to secs. 34 & 35, T. 3 N. R. 34 E. and set basalt stone 18 x 10 x 8 ins. 12 ins. in the ground for closing cor. to secs. 2 & 3, marked C. C. on S., with 2 notches on E and 4 notches on W. face; dug pits S. E. and W. of stone 5½ ft. dist., raised mound of earth 2 ft. high, 4½ ft. base over it.