

Subdivisions, T. 2 N., R. 34 E.

Chains	<p>over it. Pits impracticable.</p> <p>Land, high and rolling. Soil, 4th class & rocky.</p> <p>Grass, good. No timber.</p>	
	<p>East on random bet. secs. 28 & 33.</p> <p style="text-align: right;">Var. 18° East.</p>	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
79.75	Intersect N & S line at cor. to secs. 27, 28, 33 & 34,	
	Thence	
	West on true line	Var. 20 $\frac{1}{4}$ ° East
15.75	Gulch N.W. and ascend.	+250
28.00	Top ridge N.W. and descend.	+400
39.87	Set basalt stone 10 x 10 x 8 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face and raised mound of stone over it. Pits impracticable.	
54.40	Canyon N.	-800
	Ascend.	
79.75	Cor. to secs. 28, 29, 32 & 33.	
	Land, rough and mountainous 79.75 chs.	
	Soil, rocky, second rate. Grass, good.	
	<p>North bet. secs. 28 & 29.</p> <p style="text-align: right;">Var. 19° East.</p>	
	Descend sloping ridge.	
40.00	Set basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 ins. N & S of cor. 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.	
66.70	Dry bed of creek N.W.	
	Ascend.	
80.00	Set basalt stone 16 x 10 x 8 ins., 10 ins. in the ground for cor. to secs. 20, 21, 28 & 29, marked with 2 notches on S and 4 notches on E. edges; raised mound of stone over it. Pits impracticable.	
	Land, rolling. Soil, 4th rate. Good bunch grass.	
	Sept. 3rd, 1887.	