

## Subdivisions, T. 2 N., R. 34 E.

80.00	<p>square, 12 ins. in ground, marked 1/16 S on W. face.</p> <p>Set basalt stone 16 x 10 x 8 ins., 11 ins. in the ground for cor. to secs. 16, 17, 20 &amp; 21, marked with 3 notches on S. and 4 notches on E. edges and raised mound of stone over it. Pits impracticable.</p> <p>Land, rough and mountainous 80 chs.</p> <p>Soil, 1st and 2nd rate. Bunch grass.</p>	
79.50	<p>East on ran. bet. secs. 16 &amp; 21</p> <p>Var. 19° East.</p> <p>Set temporary cors. at 20, 40 and 60 chs., and at Intersect N and S line 40 lks. S. of cor. to secs. 15, 16, 21 &amp; 22,</p> <p>Thence</p> <p>S.89° 43' W. on true line.</p> <p>Var. same.</p>	
12.50	Gulch N.	-100
19.87	<p>Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground, marked 1/16 on N. face for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E &amp; W of stone 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.</p>	
39.00	Gulch N.	-50
39.75	<p>Set basalt stone 16 x 10 x 6 ins., 11 ins. in the ground for ¼ sec. cor., marked ¼ on N. face and raised mound of stone over it. Pits impracticable.</p>	
50.00	Top of ridge N.	+100
59.62	<p>Set basalt stone 18 x 16 x 4 ins., 12 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face; raised mound of stone over it. Pits impracticable.</p>	
79.50	<p>Cor. to secs. 16, 17, 20 and 21.</p> <p>Land, somewhat rolling and hilly.</p> <p>Soil, 1st rate. Good grass.</p>	
	<p>North bet. secs. 16 &amp; 17.</p> <p>Var. 19° East.</p>	