

Subdivisions, T. 2 N., R. 34 E.

Chains		
53.00	Canyon N.W. Descend.	-100
60.00	Enter snow brush.	
64.00	Leave same.	
80.00	Set basalt stone 10 x 8 x 8 ins., 6 ins. in the ground for cor. to secs. 19, 20, 29 & 30, marked with 2 notches on S. and 5 notches on E. edges and raised mound of stone over it. Pits impracticable. Land, high, rough and mountainous 80.00 chs. Soil, 2nd rate and some rocks. Good bunch grass. Only fit for pasture.	
<hr/>		
	East on ran. bet. secs. 20 & 29. Var. 21° East.	
40.00	Set temporary $\frac{1}{4}$ sec. corner and at	
79.90	Intersect N & S line 14 lks. S. of cor. to secs. 20, 21, 28 & 29. Thence S.89° 54' W. on true line. Var. 20° East.	
4.00	Descend abrupt bank.	
4.65	Branch 5 lks. N.W. Ascend steep ridge.	-200
26.50	Summit N.W. Descend.	+300
39.95	Set basalt stone 10 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face and raised mound of stone over it. Pits impracticable.	-400
40.75	Gulch, N. Ascend.	-500
60.00	Top ridge N. Descend gradual slope.	+500
79.90	Cor. to secs. 19, 20, 29 & 30. Land, mountainous, 79.90 chs. Soil, 2nd rate. Some shell rock. Grass, fair.	
	Sept. 5th, 1887.	