

## Subdivisions, T. 2 N., R. 34 E.

Chains	
79.80	<p>Set temporary cors. at 20, 40 and 60 chains, and at Intersect N &amp; S line 50 lks. N. of cor. to secs. 4, 5, 8 &amp; 9,</p> <p style="text-align: center;">Thence</p> <p>N. 89° 39' W. on true line. <span style="float: right;">Var. same.</span></p>
7.00	Ascend bluff S.E.
7.50	Wagon road S.E. & N.W.
12.50	Enter field.
19.95	<p>Set basalt stone 10 x 8 x 6 ins., 7 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face; dug pits 18 x 18 x 12 ins. E &amp; W of stone 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.</p>
21.15	Leave field.
30.50	O. R. & N railroad S.W.
39.40	<p>Umatilla river S.W. 80 lks. Set basalt stone 12x10x8 ins., in ground on E. bank at a point due E. of true corner, 50 lks. dist. for witness cor. to ¼ sec. cor., marked ¼ W.C. on N. face and raised mound of stone 2 ft. high, 3½ ft. base over it. Pits impracticable.</p>
39.90	Point for ¼ sec. cor. in middle of river.
45.50	Umatilla river bends N.W.
59.85	<p>A cottonwood, 6 ins. in diam., which I mark 1/16 S on N face for 1/16 S on N face for 1/16 sec. cor. and raise mound of stone 2 ft. high, 4½ ft. base around it. Pits impracticable.</p>
79.80	<p>Cor. to secs. 5, 6, 7 and 8.</p> <p>Land, mostly level. Soil, gravelly, 2nd rate.</p> <p>Timber, cottonwood and balm along river and heavy thorn and brush 20 chs.</p>
	<p>West on ran. bet. secs. 6 &amp; 7.</p> <p style="text-align: right;">Var. 20° 50' East.</p> <p>Set temporary cors. at 20, 40 and 60 chains and at</p>