

Subdivisions, T. 2 N., R. 34. E.

Chains	
84.50	Intersect Tp. line 50 lks. N. of cor. to secs. 1, 12, 6 & 7, Thence N 89° 40' East on true line. Var. 19-3/4° East.
24.50	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. cor., marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E & W. of post 5 1/2 ft. dist., and raised mound of stone and earth 1 1/2 ft. high, 3 1/2 ft. base over it.
31.50	Touch river running W.
36.50	Leave same.
44.50	Set basalt stone 12 x 10 x 10 ins., 8 ins. in the ground for 1/4 sec. cor., marked 1/4 on N face, from which A balm 10 ins. diam. bears N 60° E. 17 lks. dist., marked 1/4 S. B. T. A balm 8 ins. diam. bears S 40°57 lks. dist., marked 1/4 S. B. T.
62.00	Umatilla River runs S.W. 100 lks.
64.50	Set stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face and raised mound of stone over it. Pits impracticable.
84.50	Cor. to secs. 5, 6, 7 & 8. Land, mostly river bottom. Soil, 2nd rate & rocky in bottom; 1st rate on rolling ground. Good grass. Timber, balm and cottonwood and heavy brush. Thorn &c., along river 34.50 chs.
<hr/> North bet. secs. 5 & 6.	
Var. 20° 50' East.	
20.00	Set a post 3 ft. long, 3 ins. square with marked stone 12 ins. in the ground for 1/16 sec. cor, marked 1/16 S on W. face; dug pits 18 x 18 x 12 ins. N & S of post 5 1/2 ft. dist.; raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base around it.