

South Boundary of T. 3 N., R. 35 E.

Chains

Land, hilly.
Soil, 2nd rate.

Exterior Lines of T. 2 N., R. 36 E.
Surveyed by Herman D. Gradon under contract No. 452.
Dated June 16, 1882.
(West Boundary)

From the cor. to Tps. 1 and 2 N., Rs. 35 and 36 E., which is a post 4 ins. square, marked T 2 N R 36 E S 31 on N.E., T 2 N R 35 E S 36 on N.W., T 1 N R 35 E on S.W. and T 1 N R 36 E S 6 on S.E. faces with 6 notches on each edge, from which,

A fir, 14 ins. diam., bears N.5°W., 21 lks. dist., marked T 2 N R 35 E S 36 B T.

A fir, 20 ins., diam., bears S.52°W., 31 lks. dist., marked T 1 N R 35 E S 1 B T.

I run

North between secs. 31 and 36.

Var. 20 $\frac{1}{2}$ °E.

Descend about 100 ft. to

7.00 A spring branch, 2 lks. wide, runs N.E.

40.00 Set a basalt stone, 20x15x4 ins., 15 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face, and raised a mound of stone alongside.

46.00 Top of ridge, about 500 ft. above branch, course E.

Descend along steep side hill.

80.00 Set a post, 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 30, 31, 25 and 36, marked T 2 N S 30 on N.E., R 36 E S 31 on S.E., R 35 E S 36 on S.W. and S 25 on N.W. faces, with 1 notch on S. and 5 notches on N. edges, from which,

A cottonwood, 7 ins. diam., bears S.65°W., 39 lks. dist., marked T 2 N R 35 E S 36 B T.

No other tree within limits.

And raised a mound of stone around post.

Land, rough and mountainous.

Soil, sandy loam, 2nd rate.

Timber, scattering fir and pine. Dense undergrowth of fir, pine and buck brush.