

East Boundary of T. 2 N., R. 35 E.

Chains 69.20	<p>Intersect North bdy., 110 lks. W. of cor. to Tps. 3 N., R. 35 and 36 E. Set a basalt stone, 14x10x7 ins., 9 ins. in the ground, for closing cor. to Tps. 2 N., R. 35 and 36 E., marked C C on S. and 6 notches on S. E. and W. edges. Raised mound of stone alongside.</p> <p>Pits impracticable.</p> <p>Land, mountainous. 69.20 chs.</p> <p>Soil, rocky, 4th rate.</p> <p>No timber. Poor grass.</p> <p style="text-align: right;">September 27, 1887.</p>	
	General Description	
	<p>This Tp. is very rough and mountainous; on S. and W. only useful for grazing. There is some fair timber but inaccessible. Water can only be found in deep canyons.</p>	
	<p>Exterior Line of T. 3 N., R. 35 E. Surveyed by Currin and Noland under special contract. Dated May 4, 1887. (South Boundary)</p>	
	<p>From cor. to Tps. 3 N., Rs. 34 and 35 E. I run E. on random on S. bdy. of T. 3 N., R 35 E., at each 40 and 80 chs. set temporary $\frac{1}{4}$ sec. and sec. cors. and at 6 miles intersect 138 lks. South of corner to Tps. 3 N., Rgs. 35 and 36 E.</p> <p>Thence I run</p> <p>S.89°50'W. on S. bdy. of sec. 36, T 3 N., R. 35 E. Var. 18°45'E.</p>	
11.40	Canyon, course N.	-150
21.40	Summit of ridge.	+200
40.00	Set a basalt stone, 20x8x8 ins., 15 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{2}$ on N. face. Raised a mound of stone over it. Pits impracticable.	
42.80	Canyon, course N.W.	-100
67.40	Trail, course N. and S.	
72.40	Creek, 12 lks. wide, course N.	-300
80.00	Set a basalt stone, 18x12x4 ins., 12 ins. in the ground, for cor. to secs. 35 and 36, marked 1 notch on E. and	