

Subdivisions of T. 2 N., R. 35 E.

Chains		
	<p>high with $4\frac{1}{2}$ ft. base.</p> <p>Pits impracticable.</p> <p>Land, very rough and mountainous. 80 chs.</p> <p>Good grass.</p> <p>Soil, 4th rate.</p>	
	<p>North on true line between secs. 23 and 24.</p> <p style="text-align: center;">Var. 20° East.</p>	
3.50	Gulch, course East.	-50
10.00	Top of ridge.	+50
40.00	<p>Set basalt stone, 7x8x9 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, over which I raised a mound of stone 18 ins. high with $3\frac{1}{2}$ ft. base. Pits impracticable.</p> <p>Descend side of sloping ridge.</p>	
80.00	<p>Set a stone, 8x8x16 ins., 10 ins. in the ground, for cor. to secs. 13, 14, 23 and 24 marked with 3 notches on S. and 1 on E. edges, over which I raised a mound of stone 2 ft. high, with $4\frac{1}{2}$ ft. base. Pits impracticable.</p> <p>Land, very rough and mountainous. 80 chs.</p> <p>Some good bunch grass.</p> <p>Soil, 4th rate and rocky.</p>	
	<p>East on true line between secs. 13 and 24.</p> <p style="text-align: center;">Var. 22° East.</p>	
15.00	Top of ridge.	
40.00	<p>Set stone, 7x8x9 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, over which I raised a mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base.</p>	
70.00	Dry ditch in canyon, course S.W.	-800
80.00	<p>Intersect Township line, 3.55 chs. S. of cor. to secs. 18 and 19, T. 2 N., R. 36 E. and set a basalt stone, 7x8x9 ins., 6 ins. in the ground, for closing cor. to secs. 13 and 24 marked C C on W. face with 3 notches on N. and S. edges, over which I raised a mound of stone 2 ft. high, with $4\frac{1}{2}$ ft. base.</p>	