

## Subdivisions of T. 2 N., R. 35 E.

Chains		
45.00	Top of ridge, course N.W.	+600
52.00	Canyon, course North.	-400
	Ascend.	
73.50	Summit of divide, course N.	+1000
79.36	Intersect Township line, 3.75 chs. S. of cor. to secs. 6 and 7, T. 2 N., R. 36 E., and set a stone, 7x8x9 ins., 6 ins. in the ground, for closing cor. to secs. 1 and 12 marked C C on S. face, with 5 notches on S. and 1 on N. edges, and raised a mound of stone 2 ft. high with 4 $\frac{1}{2}$ ft. base over it. Pits impracticable.	
	Land, very rough and mountainous. 79.36 chs.	
	Soil, 3rd rate and rocky.	
	North on true line between secs. 1 and 2.	
	Var. 20°45' East.	
12.70	Gulch, course W.	-50
	Ascend.	
40.00	Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on W. face, from which,	
	A pine, 6 ins. diam., bears N.45°E., 23 lks. dist., marked $\frac{1}{4}$ S B T.	
	A pine, 18 ins. diam., bears N.75°W., 1.06 chs. dist., marked $\frac{1}{4}$ S B T.	
60.00	Creek, 20 lks. wide, course N.E.	
73.00	Intersect Township line, 40 lks. W. of cor. to secs. 35 and 36, T. 3 N., R. 35 E., and set a stone, 7x9x12 ins., 8 ins. in the ground, for closing cor. to secs. 1 and 2 marked C C on S. face with 1 notch on E. and 5 on W. edges, and raised a mound of stone 2 ft. high with 4 $\frac{1}{2}$ ft. base over it. Pits impracticable.	
	Land, rough, mountainous and brushy. 73.00 chs.	
	Pine timber in canyons.	
	Pine grass.	
	Soil, 4th rate.	