

## Subdivisions of T. 2 N., R. 35 E.

Chains	Thence S.89°55'W. on true line.	
9.00	Summit of ridge, course N.	+1500
	Descend.	
35.00	Gulch, course N.W.	-50
39.88	Set a stone, 7x8x9 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
55.00	Canyon, course N.W.	-800
65.00	Summit of ridge.	+250
79.75	To cor. to secs. 22, 23, 26 and 27. Land, extremely rough and mountainous. 79.75 chs. Soil, 3rd rate. Very little grass.	
	North on true line between secs. 22 and 23. Var. 20° East.	
4.00	Squaw Creek, 15 lks. wide, course N.W.	-1800
5.00	" " " " " " N.E.	
7.00	Leave creek bottom and ascend.	
18.00	Gulch, course E.	-50
36.00	Summit of ridge, E.	+250
	Descend.	
40.00	Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on W. face, from which, A pine, 16 ins. diam., bears N.85°E., 6 lks. dist., marked $\frac{1}{4}$ S B T. A pine, 20 ins. diam., bears S.85°W., 27 lks. dist., marked $\frac{1}{4}$ S B T.	
47.00	Canyon, course East.	-600
63.00	Top of ridge, course East.	+350
68.00	Gulch, course East.	-100
76.00	Top of ridge, course E.	+300
	Descend.	
80.00	Set a post 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 14, 15, 22 and 23 marked T 2 N S 14 on N.E., R 35 E S 23 on S.E., S 22 on S.W., and S 15 on N.W. faces with 3 notches on S. and 2 on	