

Subdivisions of T. 2 N., R. 35 E.

Chains 30.00	Gulch, course N.E.	-100
40.00	Set a stone, 8x15x21 ins., 14 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face, and dug pits, 18x18x12 ins., N. and S. from stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, with $3\frac{1}{2}$ ft. base over it.	
60.40	Fence and Indian farm.	
73.20	Intersect Township line, 10 lks. E. of cor. to secs. 34 and 35, T. 3 N., R. 35 E., and Set a post 4 ft. long and 4 ins. square, 24 ins. in the ground, for closing cor. to secs. 2 and 3 marked T. 2 N R 35 E C C on S., S 2 on E., and S 3 on W. faces, with 2 notches on E. and 4 on W. edges. Raised stone mound around it.	
	Land, rolling.	
	Soil, 1st rate.	
	Good grass. Timber in canyons.	
From the cor. to secs. 3, 4, 33 and 34 on South bdy. of Township I run North on true line between secs. 33 and 34. Var. 24° East.		
10.00	Begin to descend.	
13.00	Canyon, course East.	-200
	Ascend.	
15.00	Ridge, course East.	+100
	Descend.	
20.50	Canyon, course East.	-400
34.50	Top of hill or ridge, course East.	+600
40.00	Set stone, 7x8x10 ins., 7 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
51.50	Top of hill, course N.E.	+250
60.00	Canyon, course N.E.	-600
	Ascend.	
80.00	Set a stone, 7x8x9 ins., 6 ins. in the ground, for cor. to secs. 27, 28, 33 and 34 marked with 3 notches on E.	