

Subdivisions of T. 2 N., R. 35 E.

Chains	North on true line between secs. 3 and 4.	
	Var. 20° East.	
3.75	Gulch, course E.	-20
40.00	Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on W. face, from which,	
	A pine, 8 ins. diam., bears N.35°E., 1.33 chs. dist., marked $\frac{1}{4}$ S B T.	
	A pine, 10 ins. diam., bears N.6°W., 64 lks. dist., marked $\frac{1}{4}$ S B T.	
42.50	Ravine, course E.	-10
50.00	Wagon road, course E. and W.	
55.00	O.R. and N. Railroad, course East and West.	
60.00	Slough of water, course W.	
64.50	Umatilla River 1.25 chs. wide, course W.	
	Ascend steep bluff and leave river bottom.	
72.75	Intersect Township line, 80 lks. East of cor. to secs. 33 and 34, T. 3 N., R. 35 E., and set a stone, 8x10x12 ins., 8 ins. in the ground, for closing cor. to secs. 3 and 4, marked C C on S. face with 3 notches on E. and W. edges, and raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable.	
	Land, mountainous and river bottom. Brush and cottonwood in bottom. 72.75 chs.	
	From the cor. to secs. 4, 5, 32 and 33 on S. bdy. of Township I run	
	North on true line between secs. 32 and 33.	
	Var. 22°30' East.	
	Ascend gradual slope of mountain.	
39.00	Small gulch.	-20
	Ascend.	
40.00	Set a stone, 8x10x12 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, from which,	
	A pine, 14 ins. diam., bears South 75°W., 1.07 chs.	
	dist., marked $\frac{1}{4}$ S S T. No other trees within limits.	