

Subdivisions of T. 2 N., R. 35 E.

Chains 37.00	Branch in canyon, course W. Ascend.	-350
40.00	Set a stone, 7x10x10 ins., 7 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable. Ascend.	
50.00	Top of mountain. Descend.	+800
79.50	Gulch, dry.	-100
80.00	Set a stone, 8x10x14 ins., 10 ins. in the ground, for cor. to secs. 20, 21, 28 and 29 marked with 4 notches on E. and 2 on S. edges, and raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, mountainous and rocky. 80 chs. Scattering pine timber. Soil, 4th rate. Some grass.	
	East on random between secs. 21 and 28. Var. 21° East.	
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	
80.00	Intersect N. and S. line, 28 lks. N. of cor. to secs. 21, 22, 27 and 28. Thence N.89°48'W. on true line.	
16.50	Canyon, course S.E.	-200
35.00	Summit of ridge.	+300
40.00	Set a stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, from which, A pine, 12 ins. diam., bears N.57°W., 5.84 chs. dist., marked $\frac{1}{4}$ S B T. No other trees within limits; and raised a mound of stone over stone.	
48.80	Road, course N.W.	
80.00	To cor. to secs. 20, 21, 28 and 29.	