

## Subdivisions of T. 2 N., R. 35 E.

Chains		
13.00	Canyon, course North.	-250
27.00	Top of ridge, course North.	+250
	Descend.	
37.50	Gulch in canyon, course N.W.	-250
40.25	Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on N. face, from which, A tamarack, 18 ins. diam., bears N.70°E., 14 lks. dist., marked $\frac{1}{4}$ S B T. A tamarack, 16 ins. diam., bears S.26°E., 43 lks. dist., marked $\frac{1}{4}$ S B T.	
45.00	Top of ridge, course N.W.	+500
59.00	Canyon, course N.	-500
71.00	Top of ridge, course N.W.	+500
72.25	Wagon road and trail, N.W.	
80.50	To cor. to secs. 16, 17, 20 and 21. Land, mountainous and rocky.. 80.50 chs. Pine and tamarack timber in canyons. Soil, 1st rate.	
	North on true line between secs. 16. and 17. Var. 21°45' East.	
40.00	Set a stone, 7x8x9 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable. Descend gradual sloping ridge.	
80.00	Set a stone, 8x10x18 ins., 12 ins. in the ground, for cor. to secs. 8, 9, 16 and 17 marked with 4 notches on S. and E. edges, and raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, rolling and rocky. No timber or grass. Soil, poor, 4th rate.	
	September 9, 1887.	